




“कला संस्कृतियुक्त, स्वच्छ समुन्नत टोखा नगर”

टोखा नगरपालिका
द्वाद्वा नगबसालिका

नगर कार्यपालिकाको कार्यालय

पत्र संख्या: ०८२/६३ (योजना तथा अनुगमन शाखा)

च.नं.: ५०६५



मैजुहिटी, काठमाडौं
बागमती प्रदेश, नेपाल।

मिति: २०८३/०२/२६

ने.सं.: ११४६ अनलागा ९ मंगलवार

श्री सम्बन्धित व्यावसायीहरू

बिषय — दररेट पेश गर्ने सम्बन्धमा ।

वडा नं. ७ स्थित प्रयाशनगरमा खानेपानी पाईप विस्तार कार्यको लागि विनियोजित बजेटको कार्यक्रम कार्यान्वयनको लागि तयार भएको संलग्न BOQ अनुसारको सामग्रीहरूको दररेट उल्लेख गरी तपशिलको मिति, समय र स्थानमा तपशिलका कागजातहरू सहित प्रस्ताव पेश गर्नु हुन अनुरोध छ ।

प्रस्ताव साथ संलग्न गर्नु पर्ने कागजातहरू:

१. सम्बन्धित फर्म/ कम्पनिको निवेदन
२. कम्पनि / फर्म दर्ता नविकरण प्रमाणपत्रको प्रतिलिपी
३. भ्याट दर्ता प्रमाणपत्र
४. आ.ब.२०८१/८२ को करचुक्ता प्रमाणपत्र
५. कार्यालयबाट जारी संलग्न BOQ मा फर्मको छाप र आधिकारीक व्यक्तिको दस्तखत हुनुपर्ने ।
६. संलग्न Technical Specifications fully comply गरी सहिछाप गरेको हुनु पर्ने ।

खामबन्दी प्रस्ताव पेश गर्नु पर्ने अन्तिम मिति,समय र स्थान		प्रस्ताव खोलिने मिति, समय र स्थान	
मिति	२०८३/२/२९ गते	मिति	२०८३/०२/२९
समय	मध्यान्ह १२:०० वजे भित्र	समय	दिनको १:०० वजे
स्थान	टोखा नगरपालिका कार्यालय, मैजुहिटी, काठमाडौं	स्थान	टोखा नगरपालिका कार्यालय, मैजुहिटी, काठमाडौं

पूनाञ्च: छनौट भई सम्झौता गर्न नआएमा कालो सूचिमा राखिने प्रकृया अगाडि बढाईनेछ । अन्य कुरा सार्वजनिक खरिद ऐन तथा नियमावली वमोजिम हुनेछ ।

(अनिल प्रसाद जोशी)

वरिष्ठ शाखा अधिकृत



Municipal Executive Office
Majjhiti, Kathmandu
Province No. 3, Nepal
Bill Of Quantities

कार्यालय वा परियोजनाको नाम:- प्रयाशनगरमा खानेपानी पाईप विस्तार
कार्यक्रम / योजनाको नाम र कार्यान्वयन हुने स्थल:- खानेपानी पाईप विस्तार, वोडा न ७

S.N.	Description of items	Quantity	Unit	Unit Rate		Amount	Remarks
				In figure	In words		
A.							
Provisional works							
1.0	Provide and installation of project information Board as specified as per instruction.	1.00	₹s.	500.00	Five hundred only.	500.00	
2.0	Unforseen items	1.00	ps	2000.00	Twenty thousand only.	20000.00	
B.							
Construction works							
3.0	Road way Excavation in all types of soil as per Drawing and technical specifications including removal of stumps and other deleterious matter, disposal of excavated material at approved environmentally safe tipping sites, etc. all complete as per specification[SS 905]*	40.50	Cum				
4.0	Providing and laying broken flat brick over 60 mm thick sand bed in including excavation sand bedding all complete as per specification.	67.50	Sqm				
5.0	Providing and laying of Plain Cement Concrete grade M15 in Foundation including formwork etc. all complete as per Drawing and Technical Specifications.	6.75	Cum				
6.0	Supplying, laying & jointing 110mm dia PE 100 Grade HDPE pipe (NS-40) PN 10	150.00	rm				

Handwritten signatures and scribbles at the top of the page.

S.N.	Description of items	Quantity	Unit	Unit Rate		Amount	Remarks
				In figure	In words		
7.0	Supplying, laying & jointing 50mm dia PE 100 Grade HDPE pipe (NS-40)	145.00	m				
8.0	GI/HDPE Flange set with adopter 4"	5.00	no				
9.0	C.I Sluice Valve	2.00	no				
10.0	GI Bend/ Ebow	1.00	no				
11.0	Rubber washer and nut bolts	1.00	Ls.				
12.0	Fitting and installation charge	1.00	Ls.				
		Sub-total without VAT					
		VAT @13%					
		Total with VAT					

Name of Firm
 Proprietor's Name :
 Address of Proprietors: