



“कला संस्कृतियुक्त, स्वच्छ समुन्नत टोखा नगर”

टोखा नगरपालिका
टोखा नगरपालिका
हाल नगरपालिका



नगर कार्यपालिकाको कार्यालय

पत्र संख्या: ०८३/८४ (योजना तथा अनुगमन शाखा)

च.नं.: ८०२



मैजुहिटी, काठमाडौं
बागमती प्रदेश, नेपाल।

मिति: २०८३/०६/०५

ने.सं.: ११४६ जलाध्व १० सोमबार

सूचना नं. ०२/००/२०८३-८४

श्री सम्बन्धित निर्माण व्यावसायीहरू

विषय — दररेट पेश गर्ने सम्बन्धी सूचना ।

वडा नं. ९ स्थित कार्यालय आसपास फुटपाथ निर्माण सम्बन्धी स्वीकृत आयोजना कार्यान्वयनको लागि तयार भएको संलग्न BOQ अनुसारको दररेट उल्लेख गरी तपशिलको मिति, समय र स्थानमा तपशिलका कागजातहरू सहित प्रस्ताव खामबन्दी गरी पेश गर्नु हुन अनुरोध छ ।

प्रस्ताव साथ संलग्न गर्नु पर्ने कागजातहरू:

१. सम्बन्धित फर्म/ कम्पनिको निवेदन
२. कम्पनि / फर्म दर्ता नविकरण प्रमाणपत्रको प्रतिलिपी
३. आ.व.२०८३/८४ को लागि नविकरण गरिएको निर्माण व्यावसायी ईजाजतपत्र
४. भ्याट दर्ता प्रमाणपत्र
५. आ.व.२०८१/८२ वा २०८२/८३ को करचुक्ता प्रमाणपत्र
६. कार्यालयबाट जारी संलग्न BOQ मा फर्मको छाप र आधिकारीक व्यक्तिको दस्तखत हुनुपर्ने ।

खामबन्दी प्रस्ताव पेश गर्नु पर्ने अन्तिम मिति,समय र स्थान		प्रस्ताव खोलिने मिति, समय र स्थान	
मिति	२०८३/०६/०८ गते	मिति	२०८३/०६/०८
समय	मध्याह्न १२:०० वजे भित्र	समय	दिनको १२:१५ वजे
स्थान	टोखा नगरपालिका, योजना शाखा	स्थान	टोखा नगरपालिका कार्यालय, मैजुहिटी, काठमाडौं

पूनः छनौट भई सम्झौता गर्न नआएमा कालो सूचिमा राखिने प्रकृया अगाडि बढाइनेछ । अन्य कुरा सावर्जनिक खरिद ऐन तथा नियमावली बमोजिम हुनेछ ।


(अनिल प्रसाद जोशी)
वरिष्ठ शाखा अधिकृत





टोखा नगरपालिका
कार्यालय कोड नं.:
Bill of Quantities

[Signature]

[Signature]

म.ले.प.फारम नं.: ५०१
साबिकको फारम नं.: NA

कार्यालय वा परियोजनाको नाम:- टोखा नगरपालिका ; (पुर्वाधार विकास) वडा नं ९

आर्थिक वर्ष: २०८३/८४

कार्यक्रम / योजनाको नाम र कार्यान्वयन हुने स्थल:- वडा नं. ९ कार्यालय आसपास फुटपाथ निर्माण

क्र.सं.	काम/सेवाको विवरण आइटम	एकाइ	परिमाण	दर(अंकमा)	दर(अक्षरमा)	जम्मा लागत	कैफियत
1	2	3	4	5	9	10	11
	Footpath works						
1.00	Dismantling of Cement Concrete Grade M-15 & M-20 existing structures like culverts, bridges, retaining walls and other structure comprising of masonry, cement concrete, wood work, steel work, including scaffolding wherever necessary, sorting the dismantled Material, disposal of unserviceable Material and stacking the serviceable Material with all lifts and lead at safe tipping site. (202)	Cum	22.70				
2.00	Road way Excavation in all types of soil as per Drawing and technical specifications including removal of stumps and other deleterious matter, disposal of excavated material at approved environmentally safe tipping sites, etc. all complete as per specification[SS 905]*	Cum	2.40				
3.00	Providing and laying broken flat brick over 60 mm thick sand bed in including excavation sand bedding all complete as per specification.	Sqm	6.00				
4.00	Providing and laying of Plain Cement Concrete grade M15 in Foundation including formwork etc. all complete as per Drawing and Technical Specifications.	Cum	0.60				
5.00	Providing and laying of M25 precast cement concrete Kerb 35 cm * 20 cm * 30 cm (H*B*L) with 12 mm thick 1:3 cement sand mortar bedding and joints including foundation excavation levelling but excluding foundation concrete for foundation or sand gravel material, all complete as per Drawing and Technical Specifications.	Rm	24.00				
6.00	Providing and Laying of 60mm thick cement concrete M35 Rectangular interlocking block (Multi colour) for footpath over 50 mm thick stone dust, etc. all complete(1401)	Sqm	56.32				
7.00	Providing and laying Crusher Run sub-base on prepared surface, mixing at OMC, and compacting to achieve the desired density, complete as per Table 12.1 grading VI, Technical Specifications.	Cum	5.76				
8.00	Collar for tree plantation	Nos	8.00				

Prepared by:

Page 1 of 2
Checked by:

Approved by:

क्र.सं.	काम/सेवाको विवरण आइटम	एकाइ	परिमाण	दर(अंकमा)	दर(अक्षरमा)	जम्मा लगत	कैफियत
9.00	Providing and laying Brick Masonry Work in Cement sand mortar (1:4) in Foundation / structure, mixing mortar with concrete mixture, First class Brick, etc all complete , as per Drawing and Technical Specifications. (SS2500)	Cum	3.21				
10.00	Providing and applying 12.5 mm thick Plaster with cement mortar 1:4 (1 cement : 4 sand) on brick work structure as per Technical Specifications.	Sqm	19.00				
11.00	M.S. black pipe truss with IS or BS section including jointing, fixing, erection & colouring with all necessary MS bed plate & shoe angles anchore bolts leas sheeting or cement grouting as per drawing & instuction all compete.	Kgs	1834.46				
12.00	Supplying and applying Two coat weather proof painting (Apex or equivalent) with one coat of cement primer of approved colour in outer side of building as per specifications and instruction of the site engineer.	Sqm	19.00				
13.00	Supplying & painting work of Two coats Enamel paint after one coat primer for windows grill	Sqm	68.40				
14.00	Miscellaneous Works(underground works, maingate refixing, etc)	LS	1.00				
क. जम्मा लगत (भ्याट बिनाको रकम)							
ख. निर्माण सामग्रीको मुल्य अभिवृद्धि १३% ले आउने रकम .रु							(ख)
भ्याट १३% सहितले आउने रकम रु.							

